

BEAUTEX FENCE

Beaumont, Texas

(409) 832-6626 • (409) 504-1476 • jason@beautextence.com

25 Years Experience

R1000310

FENCE INSTALLATION PROPOSAL

Date: 1/20/21	Job Number:	Line Marked:	Yes	No
Name/Business: Texas Forest Service		Directions to Job Site:		
Address: 3882 Hwy 69, Kountze				
Home Phone:	Business Phone:	Fax:	Cell:	

Remove 700' of existing chain link and haul away.

Install 700' of 7' chain link with 3 strands of barb wire and (2) 20' double gates.

Specs:


9ga mesh

2 3/8" x 9' line posts

4" x 10'6" corner/gate posts

1 5/8" top rail

All tubing Sch 40



\$20,650

CHAIN LINK	WOOD
Height	Height
Corner Post Size	WOOD TYPE
Gate Post Size	<input type="checkbox"/> Pine
	<input type="checkbox"/> Cedar
	# RAILS
<input type="checkbox"/> Barbwire	<input type="checkbox"/> 2
<input type="checkbox"/> Razor	<input type="checkbox"/> 3
<input type="checkbox"/> Operator	<input type="checkbox"/> 4
<input type="checkbox"/> Residential	SPECIAL
<input type="checkbox"/> Industrial	<input type="checkbox"/> Bat
<input type="checkbox"/> Vinyl	<input type="checkbox"/> Gap
SPECIAL	<input type="checkbox"/> Rot Board
	POST
	<input type="checkbox"/> 4 x 4
	<input type="checkbox"/> Metal
	GATE FRAME
	<input type="checkbox"/> Wood
	<input type="checkbox"/> Metal
	IRON
	STYLE
TOP RAIL	
<input type="checkbox"/> 1-3/8"	
<input type="checkbox"/> 1-5/8"	
<input type="checkbox"/> 2"	GRADE
LINE POST	<input type="checkbox"/> Residential
<input type="checkbox"/> 1-3/8"	<input type="checkbox"/> Commercial
<input type="checkbox"/> 1-5/8"	<input type="checkbox"/> Industrial
<input type="checkbox"/>	MATERIAL
SLIDE GATES	<input type="checkbox"/> Iron
<input type="checkbox"/> Track	<input type="checkbox"/> Aluminum
<input type="checkbox"/> Cantilever	FINALS (Style)
<input type="checkbox"/> Harvey Kit	
OLD FENCE REMOVAL	
<input type="checkbox"/> Yes	
<input type="checkbox"/> No	

PRICES GOOD FOR _____ DAYS FROM DATE OF ESTIMATE.

We hereby propose to finish labor and materials - complete in accordance with the above specifications with payment to be made as follows: 1/2 down and 1/2 upon completion. If payment is not received according to contract, BeauTex Fence has the right to repossess any and all materials installed.

All material is guaranteed to be as specified. All work is to be completed in a workmanlike manner according to standard practices. Any alterations or deviations from above specifications involving extra costs, will be executed only upon written orders and will become an extra charge over and above the estimate. All agreements are contingent upon weather, accidents, or delays beyond our control.

Customers Please Note: BeauTex Fence is NOT responsible for any damage to underground lines or any unforeseen objects underground.

Cost.....	_____
Tax.....	_____
Total Cost.....	_____
Down Payment.....	_____
Balance on Completion.....	_____
Date _____	
Signature (Estimator) _____	Jason Young
Signature (Customer) _____	(See PO)

ESTIMATE

Kountze Forest Service Fence

Clints Fencing

13049 West Port Arthur Rd
Beaumont, Tx 77705

Phone: (409) 656-0899

Email: clintsfencing@gmail.com

Estimate #

000545

Date

01/15/2021

Description

Total

7' industrial chain link fence w/ 3 strands of barbed wire

\$23,696.00

Office 700' of 7' industrial chain link fence 9 ga fabric w/ 3 strands of barbed wire 4" sch 40 gate
post & Terminals 2 3/8" sch 40 line post 1 5/8" sch 40 top rail (2) 20' DD Gates

Subtotal

\$23,696.00

Total

\$23,696.00

Kountze Forest Service Fence